



# **JAMESTOWN, OHIO**

*A Progressive Community of Farmers, Families & Friends*

Municipal Offices:  
84 Seaman Drive  
Jamestown, OH 45335-1589  
(937) 675-5311 Fax:675-3142

March 22, 2019

The Village of Jamestown is asking contractors to bid on two projects on Sycamore Street. Please provide the Village with a price for Project 1, a price for Project 2, and a third price combining Project 1 and 2 into one project. The projects are described below.

## Project 1:

1. Saw-cut the existing pavement 16" deep along the north gutter line of E. Washington Street and the south gutter line of E. Xenia Street, remove existing pavement, gravel, dirt, etc. 16" deep over an area 360' x 18', and dispose of materials at a location approved by the Village.  
(All existing curb and gutter is to remain undamaged by the contractor.)
2. Compact subgrade and proof roll to assure a good solid subgrade. The contractor should include a separate square yard bid price for 12" removal depth of existing subgrade and 12" of new 304 compacted aggregate to be used if soft subgrade is encountered. The contractor will be paid for the exact quantity of aggregate needed and used as directed by the Village.
3. The contractor is to install 12" of compacted aggregate base, 2-1/2" base asphalt, and 1-1/2" of surface asphalt on the approved subgrade. The new pavement slope is to be 1/4" per foot (2%) from centerline to 1/4" above the existing gutter plates.
4. AC is to be placed on the vertical face of the existing gutter plates after excavation and prior to 304 being installed. After the surface asphalt is complete, AC is to be installed along the asphalt/gutter plate joint and along the butt joint at E. Washington Street and E. Xenia Street.
5. There is one monitoring well in the existing pavement that is to remain.

## Project 2:

1. Replace the four catch basins at the Sycamore Street/E. Washington Street intersection with new 2-2B basins approximately 3' in depth. Saw-cut both sides of a trench between the basins installing new 12" ADS N-12 watertight pipe or equal between basins. Backfill around the pipe and basins with #8 gravel and compacted 304 aggregate from above the pipe to a point 6" below the existing asphalt elevation. Place 4" of base asphalt on

the compacted 304 and 2" of surface asphalt on the base asphalt. (AC is to be placed on all asphalt joints.)

2. The new 12" storm line is to then run from one of the south catch basins south approximately 280' and connect to an existing catch basin at the existing alley. The contractor is to cut a hole in the new and existing basins and seal the basin after the storm line is installed.
3. Backfill around the pipe with #8 gravel and compacted 304 aggregate from above the pipe to a point 4" below the existing asphalt elevation. Place 2-1/2" of base asphalt on the compacted 304 and 1-1/2" if surface asphalt on the base asphalt. (AC is to be placed on all asphalt joints.)
4. There is an existing AT&T vault that the contractor will have to run new 12" storm pipe under. The exact depth is unknown and must be determined prior to establishing slope on the new storm pipe.
5. If any curb and gutter or sidewalk is damaged or removed, it is to be replaced by the contractor.

Project 1 Lump Sum Price: \_\_\_\_\_

Project 2 Lump Sum Price: \_\_\_\_\_

Combined Price for Project 1 and 2: \_\_\_\_\_

Square yard price for 12" subgrade removal and 12" of compacted 304 installed as required and as directed by the Village: \_\_\_\_\_

Plans are not being designed. The contractor is to bid the project as described above with all questions being directed to Gordy Sargent prior to submitting a bid on the project.

Bids must be received by 4:00 PM, Friday, April 12, 2019. All bids must be sealed with the project number indicated on the envelop. Please submit bids to Mayor Watson and Council, Sycamore Project, 84 Seaman Dr. Jamestown, OH 45335.

Dale Watson

Mayor, Village of Jamestown